HASSAN DIVISION.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 19th March 1931, for restoring Mallapur Badarayanakatte minor tank R. No. 139 of Belur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

4. Each tender must be accompanied by a deposit of Rs. 100 (one hundred only) in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Mallapur Badarayanakatte minor tank Regd. No. 139" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. Rates should be noted both in figures and words.

Abstract estimate of quantities for restoring Mallapur Badarayanakatte Reg. No. 139 in Belur Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	Bund.				
1	Earthwork raising the bund with consolidation, etc.	C.yds.		2,810	
2	Gravelling the top of bund with one mile lead ...	C.yd.		75	
3	Turfing the slopes	Syd.		3,015	
4	Removing and refixing the old grade stones with figures cut and painted.	Each		10	
5	Providing and fixing new index stones ...	"		10	
6	Do Reg. No. stone ...	"		1	
7	Do B. M. stones ...	"		2	
8	Removing jungle with roots and cutting grips ...	Lump	sum		
	Sluice.				
1	Cut opening and refilling the bund	C.yd.		63	
2	Earthwork excavation	"		3	
3	Concrete in surki mortar	C.ft.		82	
4	Burnt brick in surki mortar	"		172	
5	Providing and fixing 6" slab including dressing, etc., complete.	S.ft.		94	
6	Plastering with surki mortar	Sqr.		2·19	
7	Providing and fixing 4" Dia: C. I. pipe sluice including carting etc., (carting and fixing charges only as the pipes will be supplied departmentally).	Rft.		24	
8	Drilling holes in orifice and guide slabs ...	Each		8	
9	Providing a teak wood plug and rod with locking arrangements.	Lump	sum		
10	Rough stone work	Lump	sum		
11	Clearing draft and approaches	Lump	sum		
12	Removing weeds from the tank bed	Lump	sum		

M. A. SRINIVASACHARI,
Executive Engineer.

6 E